BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34129

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/19/2018-19, Date: 06.02.2019

Providing SWM works at Kodigehalli in ward no 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B Girish ( )	
				In Figures	In Words
1	12.15	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (Page no -6, item no - 2.3)	Cum	306.0	Rupees Three Hundred Six Only
2	8.1	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS. Item No 2.15	Cum	2492.0	Rupees Two Thousand Four Hundred Ninety Two Only
3	4.05	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 465 cum machine mixed, machine mixed,concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth, including cost of all material, labour HOM Machinery curing complete as per specification,(Page. No. 13 Item No. 4.2	Cum	5329.0	Rupees Five Thousand Three Hundred Twenty Nine Only
4	5.4	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No. 4.6 of PWD SR 2018-19)	Cum	5563.0	Rupees Five Thousand Five Hundred Sixty Three Only
5	3	Providing heavy duty leaf shredder Machine (chopper Machine CMS - A)	No	190000.0	Rupees One Hundred Ninety Thousand Only
6	10	BESCOM Deposit Charges	No	14250.0	Rupees Fourteen Thousand Two Hundred Fifty Only
7	35	Organic Leaf Composter Machine	Each	13775.0	Rupees Thirteen Thousand Seven Hundred Seventy Five Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

8/03

8/03